

- For bin storage units refer to drawing 7652_0302.For fence and gate refer to drawing 7652_0302.
- For ramp and associated handrail/ railings refer to drawing 7652_0306.
- For handrail at Togo Place refer to drawing 4834_0307.

- Existing grass areas: areas to be stripped, ground leveled to be flush with adjacent kerbs and re-seeded.
 Existing walls (extent of works under review): being retained, re-pointed, damaged repaired and copes missing copes replaced.
 Indicated existing bin stores demolished and removed off.

LEGEND Extent of works Existing surfacing cleaned and repaired if required Existing steps cleaned and Existing brick wall with PCC copes retained and repaired Existing render brick wall with PCC cope retained and repaired Proposed brick wall to match existing Proposed in situ concrete wall Proposed railings to ramp Existing railings to top of the wall refurbished Proposed fence 1.2m Proposed metal gates Existing top rail to the top of wall refurbished Proposed bin storage (proprietary product) Existing manholes, gullies and tobies unblocked, cleaned and re-set to suit new surfacing where required

